



# Midleton Well – Planning & Execution

Atlantic Ireland Conference, Dublin Oct. 27th 2015

#### © 2015 PETROLIAM NASIONAL BERHAD (PETRONAS)

All rights reserved. No part of this document may be reproduced, stored in a retrieval system or transmitted in any form or by any means (electronic, mechanical, photocopying, recording or otherwise) without the permission of the copyright owner.





### **Midleton Well**


Introduction





### **Exploration Licence 04/07**

- Issued to Lansdowne Oil & Gas in Aug. 2007
- 3D Survey in 2011
- Farm-in Agreement with Kinsale Energy (KEL) Nov 2014
- Licence Assignment Feb 2015:
  - KEL: 80%/Lansdowne: 20%
  - KEL to fund 100% of Exploration Well







# Celtic Sea - History

- Wells
  - 83 wells drilled since 1970 (excluding development wells)
    - 37 wells by Marathon: 1970 2003
  - 10 gas discoveries
  - 3 oil discoveries
- Developments
  - 3 gas developments:

•	Kinsale Head	1978	(inc. SW Kinsale 1999)
---	--------------	------	------------------------


- Ballycotton 1991Seven Heads 2003
- Very little drilling in last 10 years.....Providence (Barryroe), Island Oil & Gas (Old Head, Schull)





# **Midleton Prospect**

- Northern Margin of Basin
- On-trend with producing Ballycotton Field
- Amplitude Brightening at Greensand "A"-Sand level
- Shallow Target Depth (~3,000ft. SS)
- Target Horizons: Greensand + Upper Wealden







# **Original Plan**

• Licence Obligation: Drill Well by <u>Dec 2016</u>

Site Survey

Summer 2015

Well Permits/Safety Cases

Q3/Q4 2015

• Drill Well

Summer 2016

Investigate Possible Rig-Share




# **2015 Opportunity**

- Shell Corrib Workover scheduled for June/July 2015
- Drilling Rig: "Ocean Guardian"
  - Rig had availability after Corrib
  - Already had approved Safety Case
  - Previous operations in Ireland (Shell/Serica)
- Work to be Done:
  - All Permitting
  - Site Survey
  - Well Engineering
  - Services
  - Rig Contract
- Time Window: ~6 months Feb.-July





# Organisation



### Key Service Providers:

- AGR Well Engineering
- RPS Environmental/Site Survey
- Arup Project Engineering





### **Stakeholders**

- DCENR/PAD
  - Site Survey & Well Permits
- CER
  - Safety Case Submissions
- DTTAS
  - Oil Spill/Emergency Plans
- OTHER
  - State Agencies (~20)
  - Local Agencies (Fisheries, Harbour Board)
  - Suppliers, Contractors
- Stakeholder Management Plan KEL owned



### Permits – Key Submissions

#### DCENR (PAD):

- Environmental Report
- Appropriate AssessmentGeneric/Final Well Proposal
- PUDAC

#### CER:

- Well Work Safety Case
- Non-Production Safety Case

#### **DTTAS (Coastquard):**

- Oil Spill Contingency Plan Emergency Response Plan Ship to Ship Transfer Permit

#### **Challenges:**

- Truncated timetable for preparation and submission (1-3mths).
  Schedule for key service company appointments (e.g. Drilling Fluids)











### **Timelines**

DCENR/PAD

1st Meeting: Feb 18th
 Preliminary Environmental Submissions: March 9th
 Site Survey Application: April 2nd
 ✓ Approval May 8th
 Final Well Proposal (FWP): June 26th
 ✓ Approval July 15th

CER

1st Meeting: Feb 18th
 Safety Case Submissions: April 29th
 ✓ Approval July 14th

DTTAS


1st Meeting: March 25th
 OSCP Submission: June 22nd
 ✓ Approval July 16th



# Well Design

- Possible pressure depletion in 'A' Sands (Greensands)
  - Mud weight selected to address normal pressure environment whilst minimising overbalance in case of pressure depletion
- Potential for Losses
  - Base Chalk (Fractured)
  - A Sands (if depleted)
- Hard Drilling through Chalk
  - Difficulties with top hole drilling –Chert Nodules
  - Low Penetration Rates in intermediate section
  - → Drill chalk with 12 ¼" bit
    - Slim-hole Design





### Slim-hole Approach

30" Housing

**30" Conductor Joints** 

18 3/4" WHH

20" Casing

20" x 13 3/8" X-O

13 3/8" x 9 5/8" X-O

9 5/8" Csg.

30" x 20" X-O

20" x 13 3/8" X-O

13 3/8" Shoe





39ft Nom.

### **Procurement**

AGR Kick-off Meeting:

Feb 24<sup>th</sup>

- ➤ LOGIC Contracts
- AGR Pro-forma Scopes
- > Fast Turnaround
- > LLI's identified + ordered
- Drill Rig:
  - > Enquiry Issued:

> Contract signed:

Feb 27<sup>th</sup>

June 19th

- Service Contracts
  - > 15 Enquiries
  - RCT Rules relaxed
  - Piggy-back on existing KEL Services (Logistics etc.)









### **Midleton Well**

**Operations** 





# **Site Survey**



"Polar Surveyor" - Gardline – Great Yarmouth UK

Mobilised

Survey Completed

> Report Issued

> FLO + MMO (x2) onboard

May 19<sup>th</sup>


May 27<sup>th</sup>


June 23<sup>rd</sup>





# **Site Survey**





- Analogue + Digital
- Environmental Samples 2 Well Locations
- Good Data Quality
  - Seabed + Chalk as predicted





# **Drilling**

### Ocean Guardian - Diamond Offshore



- July 15: pre-lay Anchors
- July 22: Ocean Guardian on contract
- July 29: Spud Well
- Aug 9: Reached TD
- Aug 18: Rig on tow
- Aug 27: Rig off contract
  - > 33.76 Days on hire....






# **Drilling - Highlights**

- Pre-lay of anchors worked well as any resetting of anchors was carried out offline
- Top hole drilling strategy 2 runs (possibly drill in 1 run with 36" bit/motor)
- 12-1/4" Insert bit on motor BHA drilled 1,616ft riserless through chalk section
- 8-1/2" hole drilled vertically through base chalk and both reservoir targets in one run
  - 10ppg KCL Glydril water based mud system
  - 14.13ppge FIT in base chalk




# **Drilling Performance**





# **Drilling Performance**



### Summary:

Total Duration: 33.76 daysAFE: 38.14 days

NPT: 0.52 days (2%)WOW: 1.51 days (4%)

### Breakdown(Time):

Transit from Corrib: 2.29 days

Transit to Firth of Forth: 6.71 days

Total Transit: 9 days (26%)

### Breakdown(\$):

Total Transit: 31.7%

(100% Mob/Demob) → ~40%





# **Risk Mitigation**

### Regulatory

- Early + Frequent Engagement with Regulators
- Fit for Purpose Documentation

### Stakeholder Management

- Identify players
- Be proactive

### Contracting

- Use existing frameworks, if possible
- Watch commitment schedule

#### Technical

- Economical Design
- Pragmatic Approach e.g. no well test



### Conclusions

- Successful Operation well drilled safely and without incident
- CER Process only worked because of pre-existing OG SC
  - New CER AoC (Acknowledgement of Compliance) system for Rigs essential to allow flexibility in rig tendering
- Rig/Vessel mobilisation costs are a significant proportion of budget
  - Industry needs to be more efficient:
    - > Reduced mob spend = more drilling spend
- Unlocking the Celtic Sea still a challenge......







# Thank you